

Supplemental Standards No. 1 – March 18, 2008

Section 8: C Enclosed Drainage System – 7


Add - Wrap all manhole and catchbasin joints on the outside with at least two wraps of geotextile.

Section 8: C Enclosed Drainage System – 11e

Add – Furnish all manholes with the Ingham County Drain Commissioner's cover, East Jordan Ironworks EJIW 1040 C frame and cover (Product Number NCR07-205A for the lid).

Section 10: B Connections – 5

The referenced specification section of the Rules of the Ingham County Drain Commissioner, 2005 Edition is hereby amended to read "Stormwater leads connected into manholes, catchbasins, and pipes must be cored " *whenever possible. Block and brick structures must have approval of the ENGINEER before coring. Boots are required for PVC and HDPE pipe. Concrete pipe connections must be filled with non-shrink grout, hydraulic cement or Type-M mortar, on the inside and outside of the structure with a final smooth finish and wrapped on the outside with at least two wraps of geotextile.*



Patrick E. Lindemann
Ingham County Drain Commissioner
707 Buhl Avenue
P.O. Box 220
Mason, MI 48854
(517) 676-8395

Dated this 18th of March 2008

Patrick E. Lindemann, Ingham County Drain Commissioner
Signed copy in the Office